(N) FENCE

EXPANDED PARKING AREA–
CLEAR AND GRUB, EXCAVATE 4",
PLACE, GRAD AND COMPACT
6" AGGREGATE BASE

(N) FENCE

(E) FENCE TO BE REMOVED

(E) FENCE TO BE REMOVED

EXISTING PARKING AREA–
PLACE, GRADE AND COMPACT
2" AGGREGATE BASE OVER EXISTING

(E) FENCE TO REMAIN

CONCRETE ADA
PARKING
SEE DETAIL, SHT XX

(E) STEEL ACCESS
BARRIER– RELOCATE

(N) FENCE

(N) PICNIC SITES (2)
SEE DETAIL, SHT XX

(E) FENCE TO REMAIN

1
SHT 2

(N) 6"x12"X 15 LF
CONCRETE CURB

(N) SINGLE VAULT
PRECAST RESTROOM

(N) CONCRETE WALK w/ CURB, SEE DETAIL SHT XX

(N) INTERPRETIVE STRUCTURE
ON CONCRETE SLAB
SEE DETAIL SHT XX.

(E) INTERPRETIVE DISPLAY – REMOVE AND SALVAGE TO STATE

(E) TRAIL – PLACE, GRADE AND COMPACT
2" FINE AGGREGATE OVER EXISTING
ADA SURFACE

REINSTALL STEEL ACCESS
BARRIER THIS LOCATION

(E) (2) 6" OAK,
(1) 12" OAK
TO BE REMOVED .

ESTIMATED QUANTITIES		
2" AG. BASE (exist. parking)	100	TON
6" AG. BASE (expanded parking)	250	TON
FINE AGGREGATE (trail)	25	TON
CONCRETE (4" slab)	900	FT^2
CONCRETE WALK (5' w/ curb)	50	LF
CONCRETE CURB (6" x 12")	15	LF
REMOVE POST & CABLE FENCE	150	LF
INSTALL POST & FENCE	275	LF

CALIFORNIA STATE PARKS SINCE 1864

NORTHERN BUTTES
DISTRICT
400 Glen Drive
Oroville, CA
95966

REGISTERED PROFESSIONAL ENGINEER
MATTHEW B. TEAGUE
No. 61554
Exp. 6-30-15
CIVIL
STATE OF CALIFORNIA

DESIGNED:	MT
DRAWN:	MT
CHECKED:	RR
DATE:	11/1/13

REVISIONS

BUTTE CITY PROJECT
RECREATION FACILITY AND HABITAT RESTORATION

PLAN

SHEET NO.

1 OF 3

SCALE: 1"=10'

File: C:\Users\mteag\Desktop\Butte City\PLANS.dwg Layout: facilities Date: November 04 2013 - 10:38 am User: mteag